

### Project History

- Project programmed into Marina Del Rey EWMP in June 2015
- Design completed in early 2019
- > Public meeting in April 2019
- Due to feedback in meetings, project was revised in 2020

#### CEQA

- Pursuant to the CEQA (California Environmental Quality Act) guidelines, an Initial Study (IS) was prepared and determined that a Mitigated Negative Declaration finding is appropriate
- June 22, 2020, the Notice of Intent (NOI) to Adopt a Mitigated Negative Declaration was published
- 30-day public review period was provided and comments on the IS/MND document were accepted up to July 21, 2020
- City Council Approved IS/MND on August 10, 2020

#### Measure CW

What will it be used for?

· Help keep polluted runoff from entering the Creek during the summer by diverting it to the wastewater treatment plant

 Develop and implement the Green Street Master Plan

 Provide education and outreach activities to teach children, residents, businesses and visitors why and how to prevent water pollution

> · Construct multi-beneficial regional projects with public/private entities

> > · Regularly clean City storm drain pipes and street inlets to keep trash and pollutants from reaching our waterways and beaches

· Infiltrate storm water into the ground, thereby increasing ground water supplies

> Monitor water quality in our waterways in compliance with State and Regional standards

> > · Meet State and Regional water quality requirements, thereby avoiding fines and penalties

Implement programs to reduce pollution from homes, streets, businesses and industry, such as Clean Beaches Restaurant Certification program

**Culver City** measure passed **November** 2016

\$2 million generated annually

> Water pollution reduction projects


#### What is the Project?

Divert stormwater and urban runoff from storm drain


Pretreat flows

Pump flows to subsurface storage system

Divert flows to sanitary sewer and offset median irrigation



## Project Elements



#### Pretreatment



### Pipe Installation



## Storage



## Pumps





# Traffic Control Changes due to Public Comments

- Much of construction footprint has been moved from Washington Boulevard to Glencoe
- Construction zone on Washington has been minimized to allow 2 eastbound lanes
- Left turn movement from EB Washington into east Costco driveway will be retained
- Left turn movement from WB Washington onto southbound Glencoe will be retained
- Temporary parking removal on Washington has been reduced from 72 to 22 spaces between Del Rey and Glencoe



Lane closures

Congestion

Local access issues

Transit impacts

Turning prohibitions

Commuter traffic delays


Business access

Bus stop alterations

#### Traffic Control

Washington Boulevard

Temporary loss of curb-side parking




3 lanes of travel available

Limited left turning movements

#### Traffic Control

Glencoe Avenue

Temporary loss of curb-side parking



One travel lane available

Will be phasing work to maximize parking

## Traffic Mitigation

- Close coordination with City of Los Angeles, businesses, residents and schools to adaptively manage closures
- Temporary Traffic Signal adjustments to account for disrupted traffic patterns
- Work on Washington for 9 months
- Work on Glencoe for 6 months
- Costco Gas Station Construction is scheduled for February-July 2022, completely on Costco property

## Project Budget

Estimated Project Expenses		
Design	\$500,742	
Estimated Construction	\$9,000,000	
Estimated Construction Management/Inspection Services & Geotech Svcs	\$750,000	
Operations and Maintenance (30 year project life)	\$1,700,000	
Total Estimated Project Expenses	\$11,950,742	

Proposed Project Budget		
Washington Boulevard CIP	\$5,520,000	
LA County Open Space & Park Grant Funds	\$767,136	
Costco Wholesale Corporation	\$2,140,000	
Measure W Regional Funds	\$3,600,000	
Available Funds	\$12,027,136	

#### Schedule

Milestone	Anticipated Completion Date
Advertise for Construction Bids	July 2021
Award Construction Contract	September 2021
Construction Start	January 2022
Construction Completed	November 2022

#### Contact



Sean Singletary, Senior Civil Engineer 310.253.6457 Sean.singletary@culvercity.org